Stasi Brothers Asphalt Corp.

435 Maple Ave.
Westbury, NY 11590
516-334-1229 631-ASPHALT
Fax: 516-334-1245

Proposal

Date	Estimate #
7/28/2023	127209

Name / Address	Job Location
Levittown Library 1 Bluegrass Lane Levittown, New York 11756 731-5728 X220 Fax: 520-5745	1 Bluegrass Lane Levittown, New York 11756

Qty	Unit	Description	Total
6,180	sf	Option 1) Complete Rip & Replace: Remove all existing asphalt and dispose Supply up to 6" RCA stone base Grade and compact base Adjust any castings to new grade Pave lot using 2" NYS Type 6 asphalt Compact using 5-7 ton vibratory rollers Liquid a/c edges Layout and stripe lot as required	22,300.00
6,180	sf	Option 2) Spot Mill & Pave: Create butt joints at all limits of new paving, walkways and castings. Adjust any castings to new grade if required. Clean and prep surface Spot mill as needed Overlay existing asphalt with NYS Type 6 asphalt Compact using 5-7 ton vibratory rollers Layout and stripe as required	17,500.00
		*Note: We recommend Option 1 (Complete Rip & Replace) for a better total product.	
		Remove 2 sections of railroad tie wall and replace with new.	2,800.00

Any questions, please call Sal Karim, 516-865-2299
or Email:sal@stasibrothers.com